




**KEYNOTES:**

- 1 APPROXIMATE LOCATION OF PROPOSED IRRIGATION TRENCH. CONTRACTOR SHALL SAWCUT AND REMOVE EXISTING A.C. PAVEMENT IN ACCORDANCE WITH CITY OF SACRAMENTO STANDARD DWG. NO. T-80 ON SHEET L7N-CB. REPLACE A.C. PAVEMENT WITH 4" A.C. OVER 8" A.B. IN ACCORDANCE WITH CITY OF SACRAMENTO STANDARD DWG. NO. T-80. SEE LANDSCAPE PLANS FOR ACTUAL TRENCH LOCATION.
- 2 CONTRACTOR SHALL SAWCUT EXISTING ASPHALT PAVEMENT 4 FEET FROM LIP OF GUTTER AT NEAREST CONTROL JOINTS. REMOVE EXISTING A.C. PAVEMENT, CURB AND GUTTER FOR PROPOSED IRRIGATION TRENCH. REPLACE A.C. PAVEMENT TO MATCH EXISTING (MINIMUM 4" A.C. OVER 8" A.B. OVER COMPACTED SUBGRADE). REPLACE CURB AND GUTTER TO MATCH EXISTING. SEE LANDSCAPE PLANS FOR ACTUAL TRENCH LOCATION.
- 3 CONTRACTOR SHALL SAWCUT EXISTING ASPHALT PAVEMENT 4 FEET FROM FACE OF EXISTING CURB AT NEAREST CONTROL JOINTS. REMOVE EXISTING A.C. PAVEMENT AND CURB FOR PROPOSED IRRIGATION TRENCH. REPLACE A.C. PAVEMENT TO MATCH EXISTING (MINIMUM 4" A.C. OVER 8" A.B. OVER COMPACTED SUBGRADE). REPLACE CURB TO MATCH EXISTING. SEE LANDSCAPE PLANS FOR ACTUAL TRENCH LOCATION.



**KEY MAP**  
NTS



DATE SIGNED: \_\_\_\_\_  
THESE DRAWINGS ARE NOT  
CONSIDERED FINAL UNTIL THE  
ENGINEER'S SEAL BELOW HAS  
BEEN SIGNED AND DATED.

**CONSTRUCTION DOCUMENTS  
CSUS LID STORMWATER SYSTEM  
LOT 7 NORTH SITE PLAN**

SHEET  
**L7N-C1**  
OF  
**8**

DATE: 4/24/2015

JOB NO: 1432.01


CECWEST.COM  
Project Planning • Civil Engineering • Landscape Architecture  
Davis Office  
2940 Spafford Street, Suite 200  
Davis, CA 95618  
(916) 455-2026




CALIFORNIA

CALIFORNIA STATE UNIVERSITY, SACRAMENTO


S:\Projects\1400\1432 CSUS - LID Storm Water System\AutoCAD\1432-01-Civil\_C03 SHEETS\L7N - C1 - SITE.dwg - LOT 7 N 4/19/2015 - 3:15PM Plotted by: charles



**LOT 7 NORTH - BR-4**  
BIORETENTION PLANTER 1"=10'





**LOT 7 NORTH - BR-5**  
BIORETENTION PLANTER 1"=10'



**LOT 7 NORTH - BR-6 (ADD ALTERNATIVE)**  
BIORETENTION PLANTER 1"=10'

**NOTES**


1. REFER TO SHEET L7N-C1 SITE PLAN FOR SITE CONTROL.
2. BIORETENTION PLANTER CONTROL BASED ON DIMENSIONS FROM EXISTING PAVEMENT MARKINGS AS SHOWN.



**CONSTRUCTION DOCUMENTS**  
**CSUS LID STORMWATER SYSTEM**  
**LOT 7 NORTH HORIZONTAL CONTROL PLAN**

SHEET  
**L7N-C2**  
OF  
**8**  
DATE: 4/24/2015  
JOB NO: 1432.01

CECWEST.COM  
Project Planning • Civil Engineering • Landscape Architecture  
Davis Office  
2120 20th Street, Suite 200  
Davis, CA 95618  
(916) 455-2026




DESIGNED BY: NC  
DRAWN BY: NC  
CHECKED BY: DF  
SCALE: 1" = 10'


NO.	DATE	REVISIONS	BY	APPD.

CALIFORNIA STATE UNIVERSITY, SACRAMENTO  
S:\Projects\1400\1432 CSUS - LID Storm Water System\AutoCAD\1432-01-Civil\_C03 SHEETS\L7N - C2 - CTRL.dwg - LOT 7 N 4/15/2015 - 3:18PM Plotted by: chobes






**LOT 7 NORTH - BR-4**  
BIORETENTION PLANTER 1"=10'



**LOT 7 NORTH - BR-5**  
BIORETENTION PLANTER 1"=10'



**LOT 7 NORTH - BR-6 (ADD-ALTERNATIVE)**  
BIORETENTION PLANTER 1"=10'

**KEYNOTES:**


- 1 REMOVE EXISTING VEGETATION AND ADJUST EXISTING IRRIGATION SYSTEM. REFER TO LANDSCAPE PLANS IRRIGATION IMPROVEMENTS.
- 2 EXISTING DRAIN INLET TO REMAIN.
- 3 EXISTING CURB AND GUTTER TO REMAIN.
- 4 EXISTING BARRIER CURB TO REMAIN.
- 5 EXISTING TREE TO REMAIN. REFER TO SHEET T-3 FOR TREE PROTECTION NOTES.
- 6 SAWCUT AND REMOVE EXISTING A.C. PAVEMENT TO MINIMUM LIMITS SHOWN.
- 7 RELOCATE EXISTING PARKING LIGHT. SEE SHEET L7N-C4 FOR RELOCATION IMPROVEMENTS.
- 8 REMOVE EXISTING DRAIN INLET.
- 9 EXISTING SIGN. IF IN CONFLICT WITH PROPOSED IMPROVEMENTS CONTRACTOR SHALL TEMPORARILY REMOVE SIGN DURING CONSTRUCTION AND RE-INSTALL AT CONCLUSION OF WORK.
- 10 REMOVE EXISTING STORM DRAIN LINE TO LIMITS SHOWN.
- 11 REMOVE EXISTING BARRIER CURB TO LIMITS SHOWN.
- 12 EXISTING SIGN TO REMAIN.
- 13 EXISTING TRAFFIC SIGNAL BOX. ADJUST TO FINAL GRADE.
- 14 REMOVE EXISTING PARKING LIGHT CONDUIT AND CONDUCTORS TO LIMITS SHOWN. SEE PARKING LIGHT IMPROVEMENTS ON SHEET L7N-C4.

**NOTES:**

1. INTENT OF DEMOLITION PLAN IS TO PROVIDE GENERAL SITE DEMOLITION REQUIREMENTS TO CONTRACTOR. PLAN IS NOT INTENDED TO PROVIDE DETAILED INFORMATION ON SITE REMOVAL, PROTECTION AND PHASING. CONTRACTOR SHALL BE RESPONSIBLE FOR PERFORMING SITE VISITS TO DEVELOP A DETAILED DEMOLITION PLAN IN ACCORDANCE WITH THE PROPOSED SITE IMPROVEMENTS.
2. SITE DEMOLITION INCLUDES:
  - REMOVE EXISTING ASPHALT PAVEMENT AND CONCRETE CURB.
  - REMOVE EXISTING DRAIN INLET AND STORM DRAIN LINE.
  - REMOVE EXISTING TREE INCLUDING ROOTS.
  - REMOVE/ADJUST EXISTING ABOVE GROUND AND UNDERGROUND IRRIGATION FACILITIES. COORDINATE EXTENT OF IMPROVEMENTS WITH LANDSCAPE PLANS.
  - REMOVE EXISTING PARKING LIGHT ELECTRICAL WIRE AND CONDUIT.
  - RELOCATION OF EXISTING PARKING LIGHT. INCLUDES COMPLETE REMOVAL OF EXISTING CONCRETE BASE.
3. CONTRACTOR SHALL DISPOSE OF ALL MATERIALS PROPERLY OFFSITE.
4. LIMITS OF REMOVAL SHOWN ON THESE PLANS ARE APPROXIMATE. CONTRACTOR SHALL MODIFY LIMITS OF DEMOLITION AS NECESSARY TO PROVIDE FOR NEW CONSTRUCTION, BASED ON CONTRACTOR'S METHOD OF CONSTRUCTION.
5. CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL FLAGGING FOR VEHICULAR INGRESS/EGRESS.
6. PROJECT VEHICULAR AND PEDESTRIAN ACCESS PLAN SHALL BE PREPARED BY CONTRACTOR.
7. THE TYPES, LOCATIONS, SIZES AND/OR DEPTHS OF EXISTING UTILITIES SHOWN ON THESE PLANS WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. THE CONTRACTOR IS CAUTIONED THAT ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZE, LOCATION AND DEPTH OF SUCH UNDERGROUND FACILITIES. HOWEVER, THE ENGINEER CAN ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF SUCH UNDERGROUND FACILITIES NOR FOR THE EXISTENCE OF OTHER BURIED OBJECTS WHICH ARE NOT SHOWN ON THESE PLANS. IF NO ELEVATION IS SHOWN ON THE PLANS THE CONTRACTOR SHALL ASSUME THE ELEVATION IS UNKNOWN.
8. SEE SHEET L7N-C1 FOR IRRIGATION TRENCH IMPROVEMENTS.



DATE SIGNED:  
THESE DRAWINGS ARE NOT  
CONSIDERED FINAL UNTIL THE  
ENGINEER'S SEAL BELOW HAS  
BEEN SIGNED AND DATED.



**CONSTRUCTION DOCUMENTS**  
**CSUS LID STORMWATER SYSTEM**  
**LOT 7 NORTH DEMOLITION PLAN**

SHEET  
**L7N-C3**

OF  
**8**

DATE: 4/24/2015


JOB NO: 1432.01


CEWEST.COM  
Project Planning • Civil Engineering • Landscape Architecture  
Davis Office  
2840 Spafford Street, Suite 200  
Davis, CA 95618  
(916) 455-2026




CALIFORNIA  
STATE UNIVERSITY, SACRAMENTO






- DATE SIGNED: \_\_\_\_\_
- THESE DRAWINGS ARE NOT  
CONSIDERED FINAL UNTIL THE  
ENGINEER'S SEAL BELOW HAS  
BEEN SIGNED AND DATED.
- 
- A circular professional engineer seal for the State of California. The outer ring contains the text "REGISTERED PROFESSIONAL ENGINEER" at the top and "STATE OF CALIFORNIA" at the bottom, separated by two stars. The inner circle contains the name "DANIEL A. FENOCCIO" and the number "No. C51484". Below the number, the word "CIVIL" is written.


<b>SHEET</b>	<b>L7N-C4</b>	CALIFORNIA STATE UNIVERSITY, SACRAMENTO
<b>DATE:</b>	<b>OF</b>	CALIFORNIA
JOB NO: 1432.01	<b>8</b>	
<b>CONSTRUCTION DOCUMENTS CSUS LID STORMWATER SYSTEM  LOT 7 NORTH IMPROVEMENT PLAN</b>		
<p align="right">Project Planning   • Civil Engineering   • Landscape Architecture</p> <div style="text-align: center;"> <p>■ Davis Office 2940 Spafford Street, Suite 200 Davis CA 95618 (530) 758-2026</p> <hr/> <p>■ Sacramento Office 2120 20<sup>th</sup> Street, Suite 100 Sacramento CA 95816 (916) 455-0226</p> </div>		
No.	Date	Revisions
Appd.	By	Designed by NC
		DRAWN BY NC
		CHECKED BY DF
SCALE		1" = 10'



**LOT 7 NORTH - BR-4**  
BIORETENTION PLANTER 1"=20'



**LOT 7 NORTH - BR-5**  
BIORETENTION PLANTER 1"=20'




**LOT 7 NORTH - BR-6 (ADD-ALTERNATIVE)**  
BIORETENTION PLANTER 1"=20'

### KEYNOTES

1. INSTALL STORM DRAIN INLET SEDIMENT CONTROL AND FILTER BAG PER CITY OF SACRAMENTO STANDARD DWG. NOS. Q-20 & Q-30.
2. INSTALL FIBER ROLLS PER CITY OF SACRAMENTO STANDARD DWG. NO. Q-40.


### NOTES

1. REFER TO SHEET T-3 FOR EROSION CONTROL NOTES.
2. CONTRACTOR SHALL PROVIDE CONCRETE WASHOUT AREA PER CITY OF SACRAMENTO STANDARD DWG. NO. Q-80. CONTRACTOR SHALL COORDINATE LOCATION WITH CSUS REPRESENTATIVE PRIOR TO CONSTRUCTION.
3. CONTRACTOR SHALL COORDINATE WITH CSUS REPRESENTATIVE FOR MATERIAL STORAGE LOCATION PRIOR TO CONSTRUCTION.



CECWEST.COM

Project Planning • Civil Engineering • Landscape Architecture  
 Davis Office  
 2840 Spafford Street, Suite 200  
 Davis, CA 95618  
 (530) 758-2026




**CONSTRUCTION DOCUMENTS**  
**CSUS LID STORMWATER SYSTEM**  
**LOT 7 NORTH EROSION CONTROL PLAN**  
 CALIFORNIA STATE UNIVERSITY, SACRAMENTO

SHEET  
**L7N-C5**


OF  
**8**

DATE: 4/24/2015

JOB NO: 1432.01




DATE SIGNED: \_\_\_\_\_  
 THESE DRAWINGS ARE NOT  
 CONSIDERED FINAL UNTIL THE  
 ENGINEER'S SEAL BELOW HAS  
 BEEN SIGNED AND DATED.




- NOTES:**
1. FACE SIGN TOWARD NEAREST STREET OR ACCESS POINT
  2. CONCRETE WASHOUT SHALL BE LOCATED BEHIND CURB AND 50 FT. MINIMUM FROM DRAINAGE INLETS OR WATERCOURSES

REV.	DATE	DESCRIPTION




- NOTES:**
1. INSTALL FIBER ROLLS IN A ROW ALONG A LEVEL CONTOUR.
  2. AT ENDS OF A ROW TURN THE LAST TWO FEET UP SLOPE SLIGHTLY.
  3. FIBER ROLLS SHALL BE BUTTED TIGHTLY AT THE JOINTS.
  4. DO NOT OVERLAP JOINTS.
  5. FIBER ROLLS SHALL BE INSPECTED WEEKLY AND AFTER STORMS, AND REPAIRED OR REPLACED AS NEEDED.

REV.	DATE	DESCRIPTION



- NOTES:**
1. THE MAXIMUM DRAINAGE AREA PER FILTER BAG SHALL BE NO MORE THAN 2 ACRES.
  2. THE FILTER BAG SHALL BE MANUFACTURED FROM UNRESISTANT POLYPROPYLENE, NYLON, POLYESTER, OR ETHYLENE FABRIC WITH A MINIMUM TENSILE STRENGTH OF 50 LBS PER LINEAL FOOT, AN EQUIVALENT OPENING SIZE NOT GREATER THAN .05 INCHES, AND WITH A MINIMUM FLOW RATE OF 40 GALLONS/MIN/50 FT.
  3. THE FILTER BAG MAY BE SUSPENDED FROM OR HELD IN PLACE BY THE EXISTING INLET GRATE OR OTHER APPROVED METHOD, PROVIDING NO MODIFICATION OR DAMAGE SHALL BE DONE TO THE INLET GRATE OR FRAME. THE INLET GRATE SHALL NOT BE CAUSED TO REST MORE THAN 1/2" ABOVE THE INLET FRAME (SEE DETAIL A).
  4. THE FILTER BAG MAY EXTEND TO THE BOTTOM OF THE INLET BOX PROVIDED THE OUTLET PIPE IS UNOBSTRUCTED.
  5. FLOWS SHALL NOT BE ALLOWED TO BYPASS THE BAG. THE BAG OR ITS FRAME SHALL CATCH FLOWS AT ALL SIDES OF THE INLET, EXCEPT AS SHOWN FOR FLOOD RELEASE.
  6. INLET FILTER BAGS SHALL BE INSPECTED WEEKLY AND AFTER EACH RAINFALL DURING THE WET SEASON AND MONTHLY DURING THE DRY SEASON. SEDIMENT AND DEBRIS SHALL BE REMOVED BEFORE ACCUMULATIONS HAVE REACHED ONE THIRD THE DEPTH OF THE BAG. BAGS SHALL BE REPAIRED OR REPLACED AS SOON AS DAMAGE OCCURS.
  7. THIS DETAIL IS SCHEMATIC AND MUST BE ADJUSTED FOR DIFFERENT DI TYPES.

REV.	DATE	DESCRIPTION



- NOTES:**
1. SEDIMENT TRAPPED UPSTREAM OF SEDIMENT CONTROL BMP SHALL BE REMOVED WEEKLY AND PRIOR TO A RAINFALL EVENT.
  2. PLACE BMPs TIGHTLY TOGETHER AT JOINTS TO PREVENT OR MINIMIZE SEEPAGE AT JOINTS.
  3. INLET SEDIMENT CONTROL MUST BE INSPECTED WEEKLY AND AFTER EACH STORM, AND REPAIRED OR REPLACED AS NEEDED.
  4. INLET SEDIMENT CONTROL IS REQUIRED FOR ALL D's IN ADDITION TO A STORM DRAIN INLET FILTER BAG.

REV.	DATE	DESCRIPTION

CITY OF SACRAMENTO  
 DEPARTMENT OF UTILITIES

INLET SEDIMENT  
 CONTROL

APPRO'D BY: \_\_\_\_\_ NO SCALE  
 DATE: MAY 2007 DWG. NO. Q-20

CITY OF SACRAMENTO  
 DEPARTMENT OF UTILITIES

FIBER ROLLS







APPRO'D BY: \_\_\_\_\_ NO SCALE  
 DATE: MAY 2007 DWG. NO. Q-40

CITY OF SACRAMENTO  
 DEPARTMENT OF UTILITIES

STORM DRAIN INLET  
 FILTER BAG


APPRO'D BY: \_\_\_\_\_ NO SCALE  
 DATE: MAY 2007 DWG. NO. Q-30






- NOTES**
1. LIMITS OF ASPHALT REMOVAL AND REPLACEMENT SHOWN ON THESE PLANS ARE APPROXIMATE. CONTRACTOR SHALL INCREASE SAWCUT LIMITS AS REQUIRED TO PROVIDE POSITIVE DRAINAGE AT A 1% MINIMUM SLOPE AND BASED ON CONTRACTORS METHOD OF CONSTRUCTION.
  2. LIMITS OF LANDSCAPE REMOVAL AND REPLACEMENT SHOWN ON THESE PLANS ARE APPROXIMATE. CONTRACTOR SHALL INCREASE LIMITS AS NEEDED BASED ON ACTUAL FIELD CONDITIONS AND CONTRACTOR'S METHOD OF CONSTRUCTION.


DATE SIGNED: \_\_\_\_\_  
THESE DRAWINGS ARE NOT  
CONSIDERED FINAL UNTIL THE  
ENGINEER'S SEAL BELOW HAS  
BEEN SIGNED AND DATED

[illegible]



NOTES  
1. LIMITS OF ASPHALT REMOVAL AND REPLACEMENT SHOWN ON THESE PLANS ARE APPROXIMATE. CONTRACTOR SHALL INCREASE SAWCUT LIMITS AS REQUIRED TO PROVIDE POSITIVE DRAINAGE AT A 1% MINIMUM SLOPE AND BASED ON CONTRACTORS METHOD OF CONSTRUCTION.

DATE SIGNED: \_\_\_\_\_  
THESE DRAWINGS ARE NOT  
CONSIDERED FINAL UNTIL THE  
ENGINEER'S SEAL BELOW HAS  
BEEN SIGNED AND DATED.



CONSTRUCTION DOCUMENTS  
CSUS LID STORMWATER SYSTEM  
LOT 7 NORTH SECTIONS

SHEET  
**L7N-C7**  
OF  
**8**

DATE: 4/24/2015  
JOB NO: 1432.01




CECWEST.COM  
Project Planning • Civil Engineering • Landscape Architecture  
■ Davis Office  
2840 Spafford Street, Suite 200  
Davis, CA 95618  
(530) 758-2026  
■ Sacramento Office  
2120 20th Street, Suite Three  
Sacramento, CA 95818  
(916) 455-2026


NO.	DATE	REVISIONS	BY	APPD.	DESIGNED BY _____ NC	
					DRAWN BY _____ NC	
					CHECKED BY _____ DF	
					SCALE	
NTS						

CALIFORNIA STATE UNIVERSITY, SACRAMENTO







1 BIORETENTION DRAIN INLET DETAIL  
L7N-C4 NTS




2 STORM DRAIN CLEANOUT DETAIL  
L7N-C4 NTS



PARKING LOT VIEW




PLANTER VIEW




SECTION A-A

3 BIORETENTION CURB OPENING DETAIL  
L7N-C4 NTS




REINFORCEMENT DETAILS


4 BIORETENTION PLANTER CURB DETAIL  
L7N-C4 NTS




5 BARRIER CURB DETAIL  
L7N-C4 NTS



6 LIGHT POLE BASE DETAIL  
L7N-C4 NTS



7 HANDHOLE DETAIL  
L7N-C4 NTS



NOTES:

- CONTRACTOR SHALL VARY WIDTH OF TRENCH AS NEEDED FOR IRRIGATION TRENCHING.
- CONTRACTOR SHALL INSTALL A CONTINUOUS, NON-METALLIC PLASTIC FILM, WARNING TAPE OVER UTILITY PIPE WITH APPROPRIATE MARKINGS AND COLORS BASED ON UTILITY TYPE.


DATE SIGNED: \_\_\_\_\_  
THESE DRAWINGS ARE NOT  
CONSIDERED FINAL UNTIL THE  
ENGINEER'S SEAL BELOW HAS  
BEEN SIGNED AND DATED.

REGISTERED PROFESSIONAL ENGINEER  
DANIEL A. FERDINAND  
No. C51484  
CIVIL  
STATE OF CALIFORNIA

CONSTRUCTION DOCUMENTS  
CSUS LID STORMWATER SYSTEM  
LOT 7 NORTH DETAILS

SHEET  
L7N-C8  
OF  
8  
DATE: 4/24/2015  
JOB NO: 1432.01

CECWEST.COM  
Project Planning = Civil Engineering = Landscape Architecture  
Davis Office  
2120 20th Street, Suite 200  
Davis, CA 95618  
(916) 455-2026



CALIFORNIA  
STATE UNIVERSITY, SACRAMENTO  
S:\Projects\1400\1432 CSUS - LID Storm Water System\AutoCAD\1432-01-Civil\_03a SHEETS\L7N - C8 - DETL.dwg - LOT7N 4/17/2015 - 6:49AM Plotted by: chloes